

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of work: Improvements to Drains and Laying Covering Slabs at Telecom Layout in Ward No. 05 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit		
				In Figures	In Words
1	237.29	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
2	3.83	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 13/ Item No. 4.3/ PWD SR 2018-19	Cum	5408.12	Rupees Five Thousand Four Hundred Eight and Twelve Paise Only
3	8.93	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	5627.54	Rupees Five Thousand Six Hundred Twenty Seven and Fifty Four Paise Only
4	20.40	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 26/ Item No. 5.27/ PWD SR 2018-19	Sqm	966.72	Rupees Nine Hundred Sixty Six and Seventy Two Paise Only
5	91.80	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shuttering machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Material (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	2100.00	Rupees Two Thousand One Hundred Only

Sl. No.	Approved Qty.	Description	Unit		
				In Figures	In Words
6	148.50	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406,P No. 155/ Item No. 20.18/ PWD SR 2018-19	Cum	2001.28	Rupees Two Thousand One and Twenty Eight Paise Only
7	1107.00	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications Do- Medium Porosity MORTH chapter 5, No. 158/ Item No. 21.6/ PWD SR 2018-19	Sqm	36.04	Rupees Thirty Six and Four Paise Only
8	33.21	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. P. No. 159/ Item No. 21.20.1/ PWD SR 2016-17	Cum	6429.96	Rupees Six Thousand Four Hundred Twenty Nine and Ninety Six Paise Only
9	237.29	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	60.42	Rupees Sixty and Forty Two Paise Only

Chandrashekar 6/07

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"No 8 CORRECTION NIL"
"DTJ APPROVED"
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಮುಖ್ಯ ಕಾರ್ಯದರ್ಶಿ
ಮುಖ್ಯ ವಿಶೇಷ ಅಭಿಯಂತರರು
ಮುಖ್ಯ ಮಹಾಪಾಲಿಕಾ ಅಧಿಕಾರಿ